

Dane County's continued participation in the Yahara Watershed Improvement Network (Yahara WINS) resulted in another successful year of conservation implementation in 2022. By providing planning services and technical assistance to landowners and agricultural producers throughout the watershed, Dane County was able meet and exceed phosphorus reduction goals in the Yahara Watershed.




The collaborative and innovative nature of the Yahara WINS Adaptive Management Plan supports practical, impactful implementation of con-

servation practices. This approach has again shown to provide meaningful, positive benefits to local water quality. Additionally, the increase in conservation implementation has brought added benefits such as increased wildlife habitat, carbon sequestration and enhanced flood migitation throughout the watershed.

This annual report highlights the variety of conservation practices and systems that Dane County helped plan, implement, and promote in 2022. The 136 completed conservation practices in 2022 brings the total number since 2008 to 1,190 practices. Last year, over 1 million dollars was allocated to cost share agreements in the watershed, the highest amount since 2019. This includes over \$500,000 from Dane County, distribued to landowners and operators through the Soil Health Equipment Program, Continous Cover Program and Yahara CLEAN. The total amount of acres tracked through nutrient management have also steadily increased throughout the past years. Yahara WINS continues to make a positive impact to address natural resource concerns.



Pounds of phosphorus reduced in 2022



Reduction in 2022 from newly implemented practices: 7,858.3 lbs

Reduction in 2022 from carryover practices: 14,230.8 lbs

Reach 62: 186.1 lbs
Reach 63: 1,616.3 lbs
Reach 64: 4,069.3 lbs
Reach 65: 182.2 lbs
Reach 69: 1,453.5 lbs

Total phosphorus reduced throughout the watershed: 22,089 lbs

Number by unit of completed conservation practices in 2022

Total new pounds of phosphorus removed, reported by TDML Reach within the watershed







Reach 62 → 307.4 lbs

Reach 63 → 707.1 lbs

1 Waste Storage Facility Closure 136.6 Acres of No-Till Drill 136.6 Acres of Cover Crops

Reach 64 → 3,819.6 lbs

90.3 acres of No-Till Drill1,216.2 acres of Cover Crops3.1 acres of Grassed Waterway452 feet of Underground Outlet1 Waste Storage Facility Closure1 New Waste Storage Facility

Reach 65 → 0.0 lbs

Reach 66 → 520.0 lbs

392 feet of Access Road 29.2 acres of Conservation Cover 23.1 acres of Critical Area Planting 2,793 feet of Fence 11.3 acres of Perscribed Grazing

Reach 67 → 263.6 lbs

53.3 acres of Cover Crops31.2 acres of Forage and Biomass Planting700 feet of Livestock Pipeline31.2 acres of Perscribed Grazing

Reach 68 → 657.8 lbs

144.9 acres of Cover Crops13 acres of Forage and Biomass Planting990 feet of Livestock Pipeline5 acres of Conservation Cover

Reach 69 → 1,582.8 lbs

1,152 acres of Cover Crops14,299 feet of Fence1 Grade Stabilization Structure0.3 acres of Grassed Waterway1,830 feet of Livestock Pipeline1 Stream Crossing2 Watering Facilities

Nutrient Management Planning

In agricultural operations, the use of nutrient management plans (NMP) can minimize the risk of nonpoint source pollution while still ensuring crops are receiving the nutrients they need when they need them. Properly applied nutrients can support plant production while still minimizing risk to nearby natural resources.



Dane County staff receive, review and map nutrient management plans within the Yahara watershed. Additionally, the County requires participants receiving cost share assistance through some of their conservation programs to submit nutrient management plans. Utilizing this tool is another display of Dane County's ongoing commitment to protecting water quality and soil health.

52,465 total acres tracked in 2022, including internally drained areas:

Reach 62: 3,152 Reach 66: 4,122 Reach 63: 4,341 Reach 67: 1,772 Reach 64: 26,983 Reach 68: 4,637 Reach 65: 0 Reach 69: 7,458 47,144 total acres tracked in 2022, excluding internally drained areas:

Reach 62: 3,074Reach 66: 4,093Reach 63: 4,339Reach 67: 1,700Reach 64: 24,455Reach 68: 4,589Reach 65: 0Reach 69: 4,895

Another piece of the puzzle: Practice Verification Checks



Implemented practices have a range of expected lifespans. Many of them require different amount of maintainence and attention based on their purpose, usage and other outside factors. Each year staff conduct verification checks on a predetermined number of practices to ensure they are functioning as intended and well maintained. If the prac-

tices are not, staff can provide touch up work and assistance to help get these practices back on track to be adequately addressing natural resource concerns.



In 2022, there were 8 practice verification checks completed. Only one of the practices checked was not functioning and maintained as originally intended, a 5.1 acre filter strip located in Reach 66. All other checks were functioning and maintained. This includes: 1 acre of grassed waterway in Reach 62, 2.8 acres of grassed waterway in Reach 65, 2.8 acres of Forage and Biomass Planting as well as 0.6 acres of grassed waterway in Reach 66.

This support ensures the practices implemented are continuing to function as intended and minor touch up work can be done proactively to ensure function is not impaired throughout the lifespan.

2022 Financial Data

The total amount of money allocated towards cost share funding in 2022 reached over one million dollars for only the second time in program history. The 2022 total of \$1,087,599.09 is more than double the prior year in 2021. This brings the total dollars since 2008 to over \$7.3 million. There were no state dollars allocated in 2022.

\$419,264.94

Federal dollars allocated

2018: \$463,868.59

2019: \$134,377.00

2020: \$0.00

2021: \$0.00

2022: \$419,264.94

Total last 5 years: \$1,017,510.50

\$552,846.17

County dollars allocated

2018: \$371,239.25

2019: \$1,015,076.00

2020: \$839,021.76

2021: \$404,902.45

2022: \$552,846.17

Total last 5 years: \$3,183,085.63

\$115,487.98

Other dollars allocated (Yahara WINS funding)

2018: \$0.00

2019: \$19,800.00

2020: \$0.00

2021: \$0.00

2022: \$115,487.98

Total last 5 years: \$135,287.98

Total dollars allocated towards cost share agreements in 2022

\$1,087,599.09

Percentage of 2022 total by funding source

38.6% Federal
0.0% State
50.8% County
10.6% Other

2022 BY THE NUMBERS

total cost share agreements signed throughout the watershed, including 9 federal, 0 state, 20 county and 13 through Yahara WINS

Staff provided conservation planning assistance for an additional 29 practices, this technical support and guidance helps make the implementation of practices a more accessible option for landowners and operators



conservation practices implemented during the year throughout the Yahara watershed.

Pahara watershed.

Dane County staff assisted landowners and operators with a variety of types of practices, including

livestock pipelines, perscribed grazing plans, grassed waterways, waste storage facility construction and closures, fencing and more


3 acres of various soil health practices and projects

including cover crops, no-till drill, conservation covers, planting, perscribed grazing and more... that is roughly the same size of Lake Monona!

different kinds of conservation practices implemented, with lifespans ranging from 1 to 20 years

Of the 124,966 acres of cropland in the Yahara Watershed, 42% (or 52,465 acres) was received and tracked by Dane County with nutrient management plans





52,465

Total acres of land (including internally drained) across the Yahara Watershed tracked with nutrient management plans in 2022

Total new and carryover pounds of phosphorus reduced in 2022

22,089

